

Cycling, Walking and Safer Streets Projects 2016/17

Traffic Calming / Community Schemes			
1	Perth Street/Reform Street, Blairgowrie	CWSS £4,300.00	G
	Provision of flat-topped ramp across junction to reduce vehicle speeds and encourage compliance with Zebra crossing.		
2	Airlie Street, Alyth	CWSS £3,500.00	G
	Provision of build-out at Mart Street junction to reduce vehicle speeds on Airlie Street and improve visibility from Main Street.		
3	City Centre, Perth	CWSS £10,000.00	R
	Provision of corduroy tactile paving and other minor measures to improve the city centre for pedestrians with visual and mobility impairment.		
4	George Street/Union Street, Coupar Angus	CWSS £5,400.00	G
	Provision of speed cushions approaching Zebra crossing at The Cross to reduce vehicle speeds and encourage compliance of the crossing by drivers.		
Safer Routes to Schools			
5	Gowan's Terrace, Perth	CWSS £22,600.00	G
	Provision of alternative access to North Inch Campus car park to relieve congestion at Gowan's Terrace/The Rookery junction.		
6	Main Street, Bridge of Earn	CWSS £12,000.00	G
	Provision of build-out opposite Manse Road junction to facilitate School Crossing Patroller site. Project continued into 2016/17.		
7	South Street, Milnathort	CWSS £8,000.00	G
	Provision of build-out and relocation of Belisha beacon on east side of South Street to facilitate pedestrians using Zebra crossing.		
8	School Exclusion Zones	CWSS £2,600.00 SCSP £19,500.00	G
	Provision of School Exclusion Zones at Luncarty Primary School - Arngask PS, Glenfarg - Burrelton PS - Coupar Angus PS.		
Cycle Schemes			
9	Lawgrove Place, Inveralmond	CWSS £2,000.00	A
	Provision of 2.5m wide shared use path for cyclists and pedestrians from Lawgrove Place to River Almond cycle path.		
10	Ruthvenfield Place, Inveralmond	CWSS £1,700.00	G
	Provision of 2.5m wide shared use path for cyclists and pedestrians from Ruthvenfield Place to River Almond cycle path.		

11	Kingswell Road, Longforgan	CWSS £11,400.00	G
	Provision of 2.5m wide footway on Kingswell Road to link Janet Forbes Avenue with Mary Findlay Drive. Continuation of 2015/16 project.		
12	Ardblair Trail, Blairgowrie Phase 6	CWSS £75,500.00	G
	Provision of 2.5m shared use path for cyclists and pedestrians from Elm Drive to Woodlands Road as continuation of Ardblair Trail. Project deferred from 2015/16 due to land issues.		

	Engineering Administration	CWSS £16,000.00
	TOTAL	CWSS £163,000.00 SCSP £19,500.00

G	Green – Works completed in 2016/17
A	Amber - Works delayed and not completed in 2016/17
R	Red – Works did not proceed in 2016/17